

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 51N N.R. 35 and 36W


Houghton COUNTY

DESCRIPTION OF CORNER Section corner for sections T51N, R36W 13/18 T51N, R35W

CORNER MONUMENT 1" iron pipe with 4" brass cap.

DATE MONUMENT PLACED AND WITNESSED 9-19-62

WITNESSES TO CORNER..... 10" Elm (BT) N78°E, 23½ links



CIRCLE CORNER REGISTERED

5" S. Maple (BT) N15°E, 41½ links

Geological survey bench mark S50°E, 39½ links

AND Approx. $\frac{1}{2}$ of gravel road, South, 80 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line and single proportioned distance between section corners, 1 mile to south and 1 mile to north. No original evidence.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 26, 1963
REGISTERED LAND SURVEYOR
Billy D. Buckler