

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 51N N.R. 35 & 36W


Houghton COUNTY

DESCRIPTION OF CORNER Section corner for sections 24|19
T51N, R36W 25|30 T51N, R35W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 6-13-62

WITNESSES TO CORNER..... 7" Cedar (NBT) (S19) N85°E, 38 links



8" Y. Birch (NBT)(S30) S10°E, 25 links

6" Maple (NBT)(S25) S45°W, 12 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from wood post and blazed trees in vicinity post checks fairly well with corners in vicinity and with stream. No original evidence.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 24, 1963
REGISTERED LAND SURVEYOR
Billy D. Buckler