

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 51 N.R. 35 W


Houghton COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Secs. 18-19

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/17/1966

WITNESSES TO CORNER..... 14" Hard Maple (1/4S NBT), N 52° E, 13.2 Feet



14" Hard Maple (1/4S NBT), S 30° W, 40.7 Feet

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This Corner re-established on line and by Single Proportionate measure between two Section Corners.

Found some blazes immediately South but no original evidence.

Corner lies in open hardwood.

**SURVEYOR'S SEAL**

SIGNED Billy D. Buckler DATE 8/12/1966  
REGISTERED LAND SURVEYOR