


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY
T 51 N R 35 W

DESCRIPTION OF CORNER 1/4 corner between Sections 3 and 4
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED July 1, 1969
WITNESSES TO CORNER..... Y. Birch 12 N17°E 20 1/2 lks. "1/4S, NBT"



Hamlock 8 S10 1/2°W 43 lks. "1/4S, NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed by proportionate measurement on line between section corners 39.61 chains north and 40.27 chains south, as compared to record distances of 40.00 and 40.66 chains, respectively. Found no evidence of original post or its accessories or of any replacement monument or accessories. No record landmarks nearby to check modern measurements against.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur C. Enger
REGISTERED LAND SURVEYOR

DATE

1/22/71

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68