


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD

Houghton COUNTY
T 51N R 35W

DESCRIPTION OF CORNER 1/4 corner between Sections 4 and 9
CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED July 1, 1969
WITNESSES TO CORNER..... Sugar Maple 6 S25°W 10 lks. "1/4S, MST"



Sugar Maple 7 N75°E 5 lks. "1/4S, MST"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed on line between section corners 39.91 chains to east and west (record measurement of section line is 80.00 chains). Found no evidence of original corner post or its accessories or of any replacement monument or accessories. Corner lies in line with south edge of an old homestead clearing about 8 chains west. No recorded natural features close to corner to compare modern measurements with.

SURVEYOR'S SEAL

SIGNED Arthur O. Enger DATE 1/22/71
REGISTERED LAND SURVEYOR

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68