

63

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Houghton

(County)

Located In:

Corner Code #

1. Public Land Survey

T 51N R 35W 17
T 51N R 35W 67

2. Property Controlling
in Section

S T R
S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Aug 04 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
(17) Corner common to Sections 14-15-22-23. Corner re-monumented in 1958 from original Y. Birch B.T. by Billy D. Buckler, RLS. Corner monument 1" pipe with 4" brass cap. Witnesses to corner 14" White pine S61E 122 links, 14" soft maple N68W 69 links, 7" hard maple N37E 48 links.
(67) Corner common to Sections 15-16-21-22. Corner previously recorded in 1966 by Billy D. Buckler, RLS: "This corner was replaced as set by M.C. Larsen, Hancock, Mich. Found old blazed line to East and an old fence line to West. Corner lies on East edge of old road to North and South. Corner monument is 1 1/4" x 30" iron pipe, witnesses to corner: 7" Y. Birch N18E 14.5', 11" Hard Maple N68W 37.8', 10" Y. Birch S62E 10.5'.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(17) Found the 1958 monument as described, a 1" ID iron pipe capped with a 4" brass MI Dept. of Conservation tablet, in good condition, and at record bearing and distance from the 1958 accessories recovered as follows: The White pine was recovered in good condition, the soft maple is now a 18" stump, and the hard maple is a well rotted stump in a clump of sugar saplings. The original Y. Birch BT noted in the 1958 record as being "green and in good condition" was also recovered at record bearing and distance. It is now down and very rotten. Left the monument in place and marked three new accessories as described below. Corner re-witnessed by B. Wheeler, Baraga District Office.
(67) Recovered the monument as described in 1966, in good condition, and at record bearing and distance from the 1966 witnesses, the H. Maple and the Y. Birch SE standing and in good condition. The Y. Birch NE is now gone. Left the monument in place and made two new witnesses as described below. Corner re-witnessed by B. Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(17) Found 1" pipe with 4" brass cap.
Blazed and scribed the following:
12" Hemlock N88W 28.5' "S15 NBT"
3" Maple S22W 6.5' "S22 NBT"
16" Sugar N79E 41.8' "S14 NBT"
The 1958 wit. 26" N. Pine S62E 79.8'
with old blazes. Placed a squared maple
post adjacent. Bearings are magnetic.
distances to notch in lower blaze.

(67) Found 1 1/4" iron pipe
The 1966 witnesses:
14" Sugar N63W 37.8'
10" Y. Birch S58E 10.5'
Blazed and scribed the following new
witnesses:
7" Sugar N53E 14.0' "S15 NBT"
Sugar S63W 27.1' "S21 NBT"
Bearings magnetic. Distances to notch
in lower blaze.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 2/9/98

For the Michigan Department of Natural Resources - Forest Management Division