

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Houghton
(County)

Located in:

Corner Code #

1. Public Land Survey

T. 51N R. 35W

T. R.

T. R.

T. R.

2. Property Controlling
in Section

S. T. R.

S. T. R.

3. Miscellaneous
Property in Sec.

S. T. R.

S. T. R.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Aug 04 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		14		13				
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(N6) Center of Section 15. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

(N6) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/4 corners. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a yellow plastic cap stamped "MICH DNR PS 33986". Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office. The corner is located in the NW corner of a buddy bog, approx. 30'x50', growing a number of black ash.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

(N6) Set 1" pipe with plastic cap

#33986. Blazed and scribed:

10" Maple S44E 13.0' CS BT

9" Y. Birch N75E 27.8' CS BT

6" Sugar N33W 21.9' CS BT

14" Cedar S80W 37.8' CS BT

Placed squared post adjacent. Bearings

magnetic. Dist. to notch in lower

blaze.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 2/9/98

For the Michigan Department of Natural Resources - Forest Management Division