

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Houghton
(County)

Located In:

Corner Code #

1. Public Land Survey

T R
T R
T R
T R

2. Property Controlling
in Section

S 15 T 51N R 35W 12
S 15 T 51N R 35W 14

3. Miscellaneous
Property in Sec.

S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

14 Aug 04 1997

12 Jul 10 1997

I, Stephan J. Szyszkoski, in a field survey on , 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(12-Sec. 15) South 1/16 corner, Section 15. Corner not established in the original survey. Found no subsequent record.

(14-Sec. 15) South 1/16 between Sections 15-14. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(12-Sec. 15) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner 1304.38' south and Center of Section 1304.38' north. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by D.Lampela and B.Wheeler, Baraga District Office.

(14-Sec. 15) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between Quarter corner 1329.03' north and Section corner 1329.03' south. At the position for the corner, I placed a 1" I.D.x32" iron pipe, capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following bearing trees:

14" Sugar N38W 24.8' "1/16S BT"
5" Sugar N66E 9.3' "1/16S BT"
16" Hemlock S23E 22.6' "1/16S BT"
6" Sugar S84W 11.4' "1/16S BT"

Bearings are magnetic. Dist. to notch in lower blaze. Placed a squared sugar post adjacent.

(14) Set 1" pipe with 4" MDNR cap.

Blazed and scribed the following:

6" Y. Birch S02W 22.3' "1/16S BT"
5" Sugar N43W 29.5' "1/16S BT"
7" Sugar S86E 36.4' "1/16S BT"
9" Sugar N86W 36.2' "1/16S BT"

Placed a squared post adjacent. Bearings are magnetic. Dist. to notch in lower blaze.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 2/9/98

For the Michigan Department of Natural Resources - Forest Management Division