

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Naughton

(County)

Located in:

Corner Code #

1. Public Land Survey

T 51N R 35W 65

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Aug 04 1997

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(65) Corner common to Sections 9-10-15-16. Corner re-monumented in 1969 by A.O. Enger, RLS: "Monument placed by double proportionate measurement from corners 1 mile N, S, and E, and 3 miles W....Corner monument 1" I.D. x 36" iron pipe with 4" aluminum cap, witnesses to corner 8. Ash 16 N85W 32.5 links, 8. Ash 18 S13W 46 links, Red Maple 7 S35E 34 links, Elm 14 N70E 42 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(65) Recovered the 1969 monument in good condition and at record bearing and distance from the remaining 1969 witnesses. The 8. Ash 16 is now 18" dbh, the 8. Ash 18 is now 26" dbh, the Maple was found a Sugar maple 9" dbh, and the Elm is now a moss covered stump. I relocated the monuments used to control the double proportionate position of this monument and resurveyed them to check this monument's position. I determined that the dpa position is approx. N46E 14' from this monument. I note that the terrain in this area is very rugged and this most likely accounts for the variance with the record. I accept the monument as a careful and faithful reestablishment of the position of the original corner. Re-measured the NBTs and marked one new as described below. Corner re-witnessed by B. Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(65) Found 1" iron pipe with 4" HDNR cap. The 1969 witnesses:  
18" B. Ash N79W 21.4' old blazes  
26" B. Ash S17W 29.8' old blazes  
9" Sugar S31E 22.2' old blazes  
New NBT:  
10" Y. Birch N80E 2.5' "S10 NBT"  
Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 2/9/98

For the Michigan Department of Natural Resources - Forest Management Division