

57

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Noughton

(County)

Located in:

Corner Code #

1. Public Land Survey

T R

T R

T R

T R

2. Property Controlling  
in Section

S 15 T 51W R 35W 2

S 15 T 51W R 35W 10

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Aug 04 1997

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
(2-Sec. 15) East 1/16 corner between Sections 10-15. Corner not established in the original survey. Found no subsequent record.  
(10-Sec. 15) South 1/16 corner between Sections 15-16. Corner established in 1969 by A.O. Enger, RLS: "Monument placed on line between section corner 19.805 chains south and 1/4 corner 19.805 chains north. Found no evidence that the corner had ever been established previously. Corner lies on south-facing slope of a high, steep ridge running east and west. Corner monument is 1" I.D. x 36" iron pipe with 4" aluminum cap. Witnesses to corner Red Maple 7 N1.5W 38.5 links, Red Maple 7 N65E 43 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

(2-Sec. 15) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a line of mean true bearing between Quarter corner 1319.01' West and Section corner 1319.01' East. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by B.Wheeler and D.Lampela, Baraga District Office.

(10-Sec. 15) Recovered the 1969 monument, as described, in good condition, and at record bearing and distance from the 1969 witnesses, both alive and in good condition. Determined that the monument is 19.683 ch. south of the 1/4 corner and 19.652 ch. north of the section corner. I attribute this difference with the record to be the result of measuring difficulties over the harsh terrain along this line and accept the monument as a careful and faithful establishment of the position of the corner. Left the monument in place and marked two new accessories as described below. Corner re-witnessed by B.Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

(2) Set 1" pipe with 4" MDNR cap.  
Blazed and scribed the following:  
8" Sugar N05W 10.4'  
6" Sugar N62E 10.8'  
12" Sugar S44E 8.9'  
20" Neelock S71W 27.6'  
Bearings are magnetic. Dist. to notch in lower blaze.

(10) Found 1" pipe with 4" MDNR cap.  
The 1969 witnesses: 14" Red Maple N03W 38.5 links, with grown over blazes, and 10" Red Maple N68E 43 links with bottom blaze visible. Blazed and scribed the following new bearing trees:  
4" Sugar S45E 11.6' "1/16S BT"  
14" R. Maple N84W 48.9' "1/16S BT"  
A squared 2" maple bears S26W 2.9'.  
Bearings are magnetic. Dist. to notch in lower blaze.



Signed by Stephan J. Szyszkoski

Date 2/9/98

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division