

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Noughton

Located In:

Corner Code #

(County)

1. Public Land Survey

T 51N R 35W H7

T R

T R

T R

**2. Property Controlling
 In Section**

S 15 T 51N R 35W 5

S T R

**3. Miscellaneous
 Property in Sec.**

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Aug 04 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(H7) Quarter corner common to Sections 15-22. Corner established in 1848 by S.W. Higgins: "Set 1/4 Section post Sugar 10 S48E 15, do 10 N50W 20". Corner re-monumented in 1958 by Billy D. Buckler, RLS: "Replaced from two original B.T.s. Hard Maple bearing N50W 20 links and soft maple S48E 15 links. Both trees green and in fair condition. Found iron pipe in place. Corner found by L. Stevens, District Forester. Corner monument 1" pipe with 4" brass cap. Witnesses to corner, 8" Hemlock N45E 41 links, 10" Cedar S08W 67 links".

(S-Sec. 15) North 1/16 corner Section 15. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H7) Recovered the 1958 monument as described, a 1" ID iron pipe capped with a 4" brass MI Dept. of Conservation tablet, in good condition, and at record bearing and distance from both the 1958 witnesses and both original B.T.'s, all of which are green and in good condition. The original Sugar is now 20" dbh with scribing "/4 S" visible. The original Maple is 20" dbh with blaze overgrown. The 1958 cedar leans to the SE. The Hemlock (now 15") has overgrown scars top and bottom. Corner re-witnessed by B.Wheeler, Saraga District Office. The 1" pipe noted in the record was found 1.5' west of the corner.

(S-Sec. 15) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner 1315.07' North and Center of Section 1315.07 South. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. The corner is approx. 32' west of the top of a large ridge running NE-SW. Corner placed and witnessed by D.Lampela and B.Wheeler, Saraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H7) Found 1" pipe with 4" brass cap.

(S) Set 1" pipe with 4" MDNR cap.

The two original B.T.'s:

Blazed and scribed the following:

20" Sugar N45W 12.9' with scribing

6" Sugar S43W 13.0'

20" Maple S44E 8.3' with old scar

10" Y. Birch N15W 14.8'

15" Hemlock N47E 26.4' with old scars

13" Maple N58E 18.8'

16" Cedar S14W 44.0' with small scars

9" Maple S81E 26.6'

Placed a 3" squared post adjacent.

Placed a squared post adjacent.

Bearings are magnetic. Distances to notch

Bearings are magnetic. Dist. to notch

in lower blaze.

in lower blaze.



Signed by Stephan J. Szyszkoski

Date 2/9/98

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division