

55

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Noughton

(County)

Located In:

Corner Code #

1. Public Land Survey	T	51N	R	35W	66
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Sec.	S	T	R		
	S	T	R		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Aug 04 1997

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
(66) Quarter corner common to Sections 15-16. Corner reestablished in 1969 by A.O. Enger, RLS. Monument placed on line between section corners 39.61 chains to north and south. Found no evidence of original post or its accessories or of any replacement monument or accessories. Corner lies on south-southwest facing slope of a high bank, trending north-northeast and south-southwest, north of the Otter River. Corner monument is 1" I.D. x 36" iron pipe with 4" aluminum cap. Witnesses to corner: Sugar Maple 8 S32E 34 links (slope dist.), Elm 8 N45W 5 links (horizontal dist.).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(66) Recovered the 1969 monument, as described, in good condition, and at record bearing and distance from the two 1969 accessories: The Sugar is in good condition with overgrown blazes, the Elm is now dead and down with no markings visible. I determined the monument to be 7.0' south of the intended 1969 position, measuring 2609.7' North and 2595.8' South to adjacent monumented section corners. I note that the terrain along the line between 15-16 is particularly rugged, there being over 100' difference in elevation between the corner and the top of the bank just 300' north. The maximum difference in elevation along this line is well over 100'. This, I think, accounts for the observed discrepancy with the record. I accept the monument as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and marked three new witnesses as described above. Corner re-witnessed by B. Wheeler, Baraga District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the

(66) Found 1" pipe with 4" MDNR cap.

The 1969 witness Sugar 14" S27E 22.4'

(slope dist) with overgrown blazes.

Blazed and scribed the following new

bearing trees:

8" Sugar S68E 16.2' (slope) "1/4S NBT"

6" Sugar N04E 6.9' (slope) "1/4S NBT"

6" Sugar West 18.4' (slope) "1/4S NBT"

Bearings are magnetic. Distances to

notch in lower blaze.



Signed by

*Stephan J. Szyszkoski*

Date

2/9/98

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division