

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Houghton

(County)

Located In:

Corner Code #

- |                                    |                           |           |
|------------------------------------|---------------------------|-----------|
| 1. Public Land Survey              | T <u>51N</u> R <u>36W</u> | <u>K5</u> |
|                                    | T _____ R _____           | _____     |
|                                    | T _____ R _____           | _____     |
|                                    | T _____ R _____           | _____     |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____     |
|                                    | S _____ T _____ R _____   | _____     |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____     |
|                                    | S _____ T _____ R _____   | _____     |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Mar 14 2000

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5										●		
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

(K5) Corner common to Sections 11-12-13-14. Reestablished in 1970 and recorded in 1972 by A.O.Enger, RLS by double proportionate measurement. Remonumented in 1990 by K.L.Sackett, RLS "Restored from the two yellow birch stumps and pushed over iron wood stump". Set 1" ID x 32" iron pipe w/4" aluminum cap. Measurement good from E-W random line 94.38', 5" Y. Birch S07W 16.6', 6" Maple S61W 31.6', 5" Maple S55E 36.1'. The 1970 record (including survey drawing on file at the MDNR office in Baraga) show bearings and distances N01-00'-21"W, 39.701; S87-24'-30"W, 40.265; S00-46'-11"E, 39.708; and S89-55'-56"E, 40.1885; all to adjacent 1/4 corners. Also, the 1/4 corners to the east and south were placed by single proportionate measurement between section corners.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K5) Did not recover the 1990 monument. Found the 1990 witness trees, in good condition, and made measurements from them to position the corner in the 1990 location. The 1990 position is at odds with measurements made by A.O.Enger in 1970. It appears that either the 1970 position was erroneously monumented, as a result of a blunder, or that the 1990 position was not an accurate perpetuation of the 1970 position. I remonumented the corner at the 1970 record position by harmonizing the 1970 record measurements to Quarter corners north, south, east, and west, and the direction of the monumented section lines to the east and south. At the position for the corner I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. The position monumented in 1990 is N71E, 13.6' from the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K5) Set 1" pipe with 4" MDNR cap.  
 Blazed and scribed the following:  
 7" Maple S69E 45.8' "S13 NBT"  
 7" Maple S46E 20.3' "S13 NBT"  
 9" Maple S52W 18.5' "S14 NBT"  
 Distances are to notch in lower blaze.  
 Power pole N47W 57.2' PK nail with tag  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 5/1/2000

For the Michigan Department of Natural Resources - Forest Management Division