

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>36W</u>	<u>M6</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>14</u> T <u>51N</u> R <u>36W</u>	<u>16</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

16 Apr 03 2000
 M6 Mar 15 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


A. Description of original monument and accessories and/or subsequent restoration:
 (M6) Quarter corner common to Section 13 T51N-R36W and 18 T51N-R35W. Reestablished midway and on line in 1962 and recorded in 1963 by Billy D. Buckler, RLS. 1" iron pipe with 4" brass cap. 6" H.Maple S30W 29 links, 8" Y.Birch S66E 14.5 links.
 (16-Sec. 14) East 1/16 corner between Sections 14-23. Established in 1971 and recorded in 1972 by A.O.Enger, RLS. 1" I.D. x 36" iron pipe with 4" aluminum cap. Sugar Maple 9 S20W 17.2', Sugar Maple 12 S75E 18.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M6) Recovered the 1962 monument, as described, a 1" ID iron pipe capped with a 4" brass State of Michigan tablet, in good condition, and at record bearing and distance from the two 1962 NBTs. The Y. Birch is now a dead stub. The Sugar is in good condition with overgrown blazes. I verified the position of the monument as being according to the 1963 record. Left the monument in place and made new witnesses as described below.
 (16-Sec. 14) Recovered the 1971 monument as described, a 1" ID iron pipe capped with a 4" dia. cast aluminum State of Michigan tablet, appropriately stamped, in good condition, and at record bearing and distance from the 1971 witnesses, both recovered in good condition with overgrown blazes. My measurements east and west to adjacent corners verifies the 1971 record. Left the monument in place and made new accessories as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M6) Found 1" pipe with 4" brass cap. The 1962 wit: 10" Sugar S37W 19.0' w/overgrown blz. Blazed and scribed the following: 12" Sugar N26E 34.8' "1/4S NBT" 9" Sugar S42E 15.2' do 19" Hemlock N71W 73.5' do Placed squared maple post adjacent. Bearings are magnetic. Distances to notch in lower blaze.	(16) Found 1" pipe with 4" alum. cap. The 1971 wits: 13" Sugar N80E 18.1' overgrown blazes 10" Sugar S21W 17.2' do Blazed and scribed the following: 7" Y.Birch N8W 34.2' "1/16S BT" 10" Y.Birch N30E 32.8' do Placed squared Sugar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.
--	--



Signed by Stephan J. Szyszkoski Date 5/1/00
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division