

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>51N</u> R <u>36W</u>	<u>K4</u>	
	T <u>   </u> R <u>   </u>	<u>   </u>	
	T <u>   </u> R <u>   </u>	<u>   </u>	
	T <u>   </u> R <u>   </u>	<u>   </u>	
2. Property Controlling in Section	S <u>13</u> T <u>51N</u> R <u>36W</u>	<u>15</u>	
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>	
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>	
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

K4 Apr 05 2000  
 15 Apr 04 2000

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		10	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(K4) Quarter corner common to Sections 11-12. Corner reestablished in 1970 by single proportionate measurement and recorded in 1972, by A.O.Enger, RLS. 1" ID x 36" iron pipe with 4" aluminum cap. Sugar Maple 8 S43E 18.2', Elm 7 S35W 13.9'.  
 (15-Sec.13) West 1/16 corner between Sections 13-24. Established in 1970 and recorded in 1972 by A.O.Enger, RLS, midway between Section and Quarter corners. 1" IDx14" iron pipe with 4" aluminum cap. Sugar Maple 15 N39:30W 66.8', Y.Birch 8 N22E 47.1'.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K4) Recovered the 1970 monument as described, a 1" ID iron pipe capped with a 4" dia. cast aluminum Michigan Dept. of Conservation tablet, appropriately stamped, in good condition, and at record bearing and distance from the 1970 witnesses. The Sugar is in good condition. The Elm is dead and down. Left the monument in place and made new witnesses as described below.  
 (15-Sec.13) Recovered the 1970 monument, about 0.2' below the surface of Pike Lake Rd, and about 2' N. of the physical centerline, with corroded and unreadable 4" aluminum cap. Otherwise, the monument is in good condition and was found at record bearing and distance from the 1970 witnesses. My measurements east and west to adjacent corners verifies the 1970 record. Left the monument in place and made new accessories as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K4) Found 1" pipe with 4" alum. cap. The 1970 witness: 11" Sugar S40E 18.2' overgrown blazes Blazed and scribed the following: 11" Sugar S25W 29.7' "1/4S NBT" 10" Y.Birch N35W 29.7' do 5" Y.Birch N39E 37.7' do Placed squared Sugar post adjacent. Bearings are magnetic. Distances are to notch in lower blaze.	(15) Found 1" pipe with 4" alum. cap. The 1970 witnesses: 11" Y.Birch N26E 46.9' overgrown blazes 15" Sugar N35W 66.7' do Blazed and scribed the following: 9" Y.Birch S58E 52.7' "1/16S BT" 8" Sugar S55W 33.0' do Bearings are magnetic. Distances are to notch in lower blaze.
--	--



Signed by Stephan J. Szyszkoski Date 5/1/00  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division