

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Houghton
 (County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|------------|-------|
| 1. Public Land Survey | T | <u>51N</u> | R | <u>36W</u> | M7 |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Mar 15 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(M7) Corner common to Sections 13-24 T51N-R36W and 18-19 T51N-R35W. Reestablished in 1962 and recorded in 1963 by Billy D. Buckler, RLS. 1" iron pipe with 4" brass cap. 10" Elm N78E 23.5 links, 5" S. Maple N15E 41.5 links, Geological Survey benchmark S50E 39.5 links, Approx. centerline of gravel road, South 80 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M7) Recovered the 1962 monument, disturbed by nearby driveway construction. About 9" of the base of the monument, including the iron cross-piece was still in place and set vertically. The remainder had been bent over by heavy equipment. The 1962 witnesses were not recovered, being within an area disturbed for the drive and a ditch. The position of the monument was verified by checking against Buckler's measure to the north to the 1/4 and Section corners, and west against A.O. Enger's measure to corners along the south line of section 13 (see previous recordations for K7 and L7). I conclude that the base of the monument has not been disturbed and occupies the 1962 position. At the position of the remains of the 1962 monument, I placed a 1" ID x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped, driven to 0.3' below the ground's surface. The center of the gravel road noted in the 1963 record (Pike Lake Rd.) is south, approx. 54 ft. The center of a M-S gravel drive is west, 6 ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M7) Set 1" pipe with 4" MDNR cap.
 Blazed and scribed the following:
 8" Y. Birch N25E 75.1' "S18 NBT"
 12" Sugar S80E 8.7' "S19 NBT"
 12" Y. Birch S35W 83.6' "S24 NBT"
 9" Sugar in clump N63W 30.2' "S13 NBT"
 Placed squared spruce post adjacent.
 Bearings are magnetic. Distances are to notch in lower blaze.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 5/1/00

For the Michigan Department of Natural Resources - Forest Management Division