

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>36W</u>	<u>L8</u>
	T <u>51N</u> R <u>36W</u>	<u>I9</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Oct 08 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L8) Center of Section 24. Not established in the original survey.

(I9) Corner common to Sections 22-23-26-27. 1962: Billy D. Buckler remonumented the corner at the position of an "old wood post set by unknown surveyor". Set 1" ID iron pipe with 4" aluminum cap. 9" Hard Maple N41W 31 links, 14" Hard Maple S51W 38 links, 10" Hard Maple S65W 38 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L8) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(I9) Recovered the 1962 monument in good condition and at record bearing and distance from the 1962 witnesses. The S65W bearing to the 10" H.Maple is a typographical error as the bearing to this tree was observed to be S65E. In any case, this tree was cut down during this survey to facilitate GPS observations. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L8) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:

8" Maple N04E 23.2' "C1/4 BT"
 9" Sugar S83E 26.9' do
 7" Sugar S10W 22.9' do
 14" Hemlock S31W 35.9' do

Set sq'd spruce post adjacent. Bearings are magnetic. Distances are to nail with tag.

(I9) Found 1" ID I.pipe with 4" alum. MI Dept. of Conservation cap. Blazed, scribed, and set measuring nails in:

15" Sugar S86E 16.4' "S26 NBT"
 8" Sugar S06E 48.8' do
 The 1962 wits:

16" Sugar S55W 25.8' overgrown blazes
 13" Sugar N36W 21.2' do
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/3/03