

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>36W</u>	<u>L11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>23</u> T <u>51N</u> R <u>36W</u>	<u>8</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File  
Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims

L11 Oct 23 2003  
 8 Oct 09 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(L11) Quarter corner common to Sections 25-36. 1848; Established by S.W. Higgins: East random between Sec 25,36...34.30 stream 1 N...80.96 Intersected E boundary 80L N of post. West corrected...40.48 Set 1/4 Section post. Sugar 6 N5E 32, Sugar 9 S72W 3...80.96 Section corner.  
 (8-Sec. 23) West 1/16 corner, Section 23. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L11) The original post and accessories were not recovered. Reestablished the corner midway and on a line of mean true bearing between Section corners 2775.69' east and west (each 1/2 mile being 1.58 ch. longer than record). From the corner position thus established, I found the stream, noted above, 1 link wide, course North, 411' West (6.23 ch. M, 6.18 ch. R), checking very well with the record.  
 (8-Sec. 23) Established the corner midway and on a straight line between Quarter corner 1328.95' west and Center of Section (unmonumented) 1328.95' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 7" Sugar N03W 27.7' "1/4S NBT" 11" dbl Maple S36E 45.5' do 8" Maple S27W 23.4' do 8" Y.Birch S80W 20.5' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.	(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 10" Sugar N36E 19.2' "1/16S BT" 12" Sugar S46E 25.1' do 10" Sugar S59W 13.8' do 10" Sugar N40W 16.2' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	---



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 11/3/03

For the Michigan Department of Natural Resources, Office of Land and Facilities