

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>36W</u>	<u>M11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 21 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M11) Corner common to Sections 25-36 T51N-R36W and 30-31 T51N-R35W. 1845: Established by Austin Burt: North on E. side Sec. 36...40.00 Set qr. Section post...80.00 Set post corner of Sections 25&36. Fir 8 S37W 8, Birch 6 N16W 6. According to a township map of T51N-R35W by P.A. Larsen and M.C. Larsen this corner was reestablished in 1913 and is shown as "post set". Distance is shown to B11 (2797.4'), C11 (5407.4'), and to A12 (2644.6'), all of T51N-R35W. Subsequent field notes, probably of M.C.Larsen state "Found wooden cedar stake Cor. 30-31. Set I.P. 16.5' N. to Fence post". Corner subsequently noted by R.W.Crampton, PS as 1" sq. iron pin. 5" Pin Cherry North 35.41', twin 10" Cedar S85E 128.07', twin 10" Spruce 107.27' [no brg.], N61W 139.00' to NE cor. of house. Distances noted by R.W.Crampton to B11, C11, and A12 are 2780.59', 5408.62', and 2639.52', respectively.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M11) Recovered a 1.25" ID iron pipe 6" below the ground surface on the C/L, produced, of Uusitalo Rd. and on the approximate extension of the remains of a very old and unmaintained fence line to the north. Distances to C11 and A12, T51N-R35W were found to be 5410.56' (Larsen +3.16') and 2642.63' (Larsen -1.97), respectively. The distance to B11 is 2786.50' (Larsen -10.9'). C11, B11, a 3/4" iron pin found in the road at corner #2, Sec. 31 51-35 (probable P.A.Larsen position and in accord with his map) and the 1.25" dia. pipe described herein all lie on a straight line, the largest offset from the line being 0.36' at corner #2, Sec. 31. The square iron bar noted by R.W.Crampton was recovered on the extension of an old and unmaintained fence to the south, flush with the ground's surface. The corner area, being immediately adjacent to Uusitalo road appears to have been filled slightly in the past, judging by the debris found in the soil during our search and excavation. I judge the 1.25" ID iron pipe to be at the Larsen position of 1913 and accept it as the Section corner. I cannot account for the 1" square bar other than to suppose that it was placed subsequent to the Larsen pipe and at the intersection of the fenceline south and the C/L extension of Uusitalo Rd. The bar was recovered S61E 6.87' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M11) Set 1" IDx32" I.pipe with 4" alum. MDNR cap driven into found 1.25" ID iron pipe. Blazed, scribed, and set measuring nails in:
 8" dbl Maple N04E 65.1' "S30 NBT"
 12" W.Spruce S70E 93.1' "S31 NBT"
 10" Cedar S15W 62.8' "S36 NBT"
 6" W.Spruce S71W 26.2' "S36 NBT"
 Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/3/03