

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>25</u> T <u>51N</u> R <u>36W</u>	<u>12</u>
	S <u>25</u> T <u>51N</u> R <u>36W</u>	<u>6</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Oct 23 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (12-Sec. 25) South 1/16 corner, Section 25. Not established in the original survey.
- (6-Sec. 25) Northeast 1/16 corner, Section 25. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (12-Sec. 25) Established the corner midway and on a straight line between Center of Section (unmonumented) 1344.06' North and Quarter corner 1344.06' South.
- (6-Sec. 25) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| (12) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: | (6) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: |
| 6" Y.Birch N30E 22.5'      "1/16S 8T"   | 5" Sugar N16W 15.8'      "1/16S 8T"  |
| 8" Spruce S11E 27.5'      do  | 8" Cedar N84E 24.0'      do  |
| 13" Spruce S80W 12.9'      do   | 5" Y.Birch S35E 24.9'      do  |
| 5" Cedar N60W 15.5'      do   | 6" Maple N75W 5.0'      do   |
| Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.          | Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.         |



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 11/3/03