

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>36W</u>	<u>83</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>7</u> T <u>51N</u> R <u>36W</u>	<u>1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

1 Dec 20 2006
 B3 Jun 18 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3		●											
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (B3) Quarter corner common to Sections 6 and 7. 1959 - Remonumented by Billy D. Buckler RLS in the original position as determined from a Tamarack B.T. N60W 18 links, stump in good condition. Set 1" iron pipe with 4" brass cap. 8" W.Pine S88E 49 links, 9" W.Pine S73E 1.17 chains.
- (1-Sec. 7) West 1/16 corner between Sections 6 and 7. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (B3) Recovered the 1959 monument in good condition. The 1959 witnesses and the Tamarack BT noted in the 1959 record were not recovered. Accepted the corner as a careful and faithful perpetuation of the position of the original corner.
- (1-Sec. 7) Established the corner on the Section line between monumented Section corner 1374.10' west and Quarter corner 1316.82' east, being 20 chains, proportionate to the original record, west of the Quarter corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (B3) Fd. 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nails in: | (1) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: |
| 4" Tamarack N26W 48.9' mrkd "1/4S NBT" | 6" Sugar N33W 24.2' mrkd "1/16S BT" |
| 2" Tamarack N67E 7.1' do | 8" Sugar S83E 21.5' do |
| 3" Tamarack S04E 9.0' do | 17" Maple S48E 19.6' do |
| 4" Tamarack S37W 23.7' do | 5" Sugar S73W 24.6' do |
| Set sq'd Tam. post adjacent. Bearings are magnetic. Distances are to nail with MDNR tag. | Set sq'd sugar post adjacent. Bearings are magnetic. Distances are to nail with tag. |



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 7/18/07