

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T 51N R 36W	K3	
	T _____	_____	_____
	T _____	_____	_____
2. Property Controlling in Section	S _____	_____	_____
	S _____	_____	_____
	S _____	_____	_____
3. Miscellaneous Property in Sec.	S _____	_____	_____
	S _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

I, Stephan J. Szyszkoski, in a field survey on 11/09/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K3) Corner common to Sections 1-2-11-12. 1970 - Reestablished by A.O.Enger RLS by proportionate measurement between corners 158.81 ch. S, 39.70 ch. N, 80.59 ch. E, and 80.19 ch.W. Set 1"IDx36" iron pipe with 4" aluminum cap buried 1"-2" below ground level just northerly of northerly track of woods road running SW and NE. Sugar Maple 16" N8E 31.4', Sugar Maple 7" S66 1/2E 50.6', W.Spruce 4" N35W 25.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K3) Found the 1970 monument in place, but top portion bent over, having been hit by heavy equipment, at record bearing and distance from the 1970 bearing trees. The Sugar NE and W.Spruce NW are in good condition with overgrown double blazes. The Sugar SE is standing dead. Measured 80.21 ch. West and 158.70 ch. South to recorded corners. I accpeted the 1970 position as a careful and faithful reestablishment of the position of the original corner. Removed the 1970 monument and in its place, at the 1970 position, placed a new monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 15" Sugar N15E 31.9' old blazes 1970 NBT
 8" W.Spruce N32W 25.5' do do
 6" Y.Birch S47E 39.2' mrkd "S12 NBT"
 9" dbl Y.Birch S04E 36.4' do
 10" Sugar (dead) S62E 50.5' to old notch
 Bearings are magnetic. Cap is 0.3' below the surface at the N. edge of SW-NE woods rd.



Signed by Stephan J. Szyszkoski Date 11/10/2009
 Surveyor's Michigan License No. 33986