

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>11</u> T <u>51N</u> R <u>36W</u>	<u>8</u>
	S <u>11</u> T <u>51N</u> R <u>36W</u>	<u>SMC N. of 8</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 06/30/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (8-Sec. 11) West 1/16 corner, Section 11. Not established in the original survey.
- (SMC N. of 8, Sec. 11) Special Meander Corner on the line between Government Lots 3 and 4, Section 11, on the south shore of Pike Lake. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (8-Sec. 11) Established the corner midway and on a straight line between Quarter corner 1342.00' West and the intersection of Quarter lines of Section 11 1342.00' East.
- (SMC) Established the West N-S 1/16 line of Section 11 (being the line between Government Lots 3 and 4) at mean bearing of the West line of Section 11 and the N-S 1/4 line of Section 11. On this line, at N00 degrees 15'42"E (true bearing), 971.11' from the West 1/16 corner (#8) of Section 11, I established this Special Meander Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
7" Hemlock N81W 15.3' mrkd "1/16S BT"
7" Maple N58W 16.7' do
6" dbl. Maple N06W 15.0' do
4" Hemlock N19E 24.7' do
Set sq'd cedar post adjacent.
Bearings are magnetic. | (SMC) Set 1"IDx36" I.pipe with 4" alum. MNDR cap.
Set measuring nail with MDNR tag in the side of:
9" Hemlock S66W 32.2' mrkd "SMC BT"
5" Maple S03W 17.9' do
8" Maple S29E 11.2' do
5" Spruce S51E 4.95' do
Set sq'd cedar post adjacent.
Bearings are magnetic. |
|--|--|

Signed by Stephan J. Szyszkoski Date 11/10/2009
 Surveyor's Michigan License No. 33986



For the Michigan Department of Natural Resources, Office of Land and Facilities