

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>34</u> T <u>51N</u> R <u>36W</u>	<u>14</u>
	S <u>34</u> T <u>51N</u> R <u>36W</u>	<u>1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 14 06/11/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(14-Sec. 34) South 1/16 corner between Sections 34 and 35. 1981 - K.L.Sackett RLS monumented the corner midway and on line between Section and Quarter corners. Set 1"IDx32" iron pipe with 4" alum. cap. 5" Sugar S40E 23.3', 7" Sugar S32W 18.0', 5" Maple N50W 10.3'.

(1-Sec. 34) West 1/16 corner between Sections 27 and 34. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14-Sec. 34) Recovered the 1981 monument in good condition and at record bearing and distance from the 1981 BTs Sugar SE and Sugar SW, both in good condition with overgrown blazes. The monument is SSE 1.9' from the midway position intended in 1981 and I accept same as a careful and faithful establishment of the position of the corner.

(1-Sec. 34) Established the corner midway and on the Section line between Section corner 1333.98' west and Quarter corner 1333.98' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 7" Sugar S34E 23.5' old blazes. 1981 BT  
 11" Sugar S38W 18.3' do do  
 10" Maple N76E 21.2' mrkd "1/16S BT"  
 5" Maple N31W 2.1' do  
 3.5' tall 1.25" ID pipe adjacent. Bearings are magnetic.

(1) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 9" Maple N12E 11.9' mrkd "1/16S BT"  
 6" Y.Birch S50E 30.0' do  
 5" Sugar S06E 16.4' do  
 4" Sugar N62W 2.4' do  
 Set sq'd cedar post adjacent. Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 08/11/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities