

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>34</u> T <u>51N</u> R <u>36W</u>	<u>9</u>
	S <u>27</u> T <u>51N</u> R <u>36W</u>	<u>11</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 9 06/10/2008 and 11 06/11/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(9-Sec. 34) East 1/16 corner, Section 34. Not established in the original survey.

(11-Sec. 27) Southwest 1/16 corner, Section 27. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(9-Sec. 34) Established the corner midway and on a straight line between Quarter corner 1320.79' east and intersection of 1/4 lines 1320.79' west, as described on a survey dated Aug. 6, 2008, Project Numbers 11-05-08 and 11-10-08, by the undersigned for the Michigan Dept. of Natural Resources.

(11-Sec. 27) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 7" Sugar N29W 21.95' mrkd "1/16S BT"  
 7" Sugar N44E 26.85' do  
 6" Sugar S07E 17.55' do  
 11" Sugar S59W 21.2' do  
 Set sq'd spruce post adjacent. Bearings are magnetic.

(11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 9" Cherry N47E 21.1' mrkd "1/16S BT"  
 10" Sugar S52E 35.0' do  
 7" Y.Birch S02E 19.1' do  
 8" Sugar S75W 20.7' do  
 Set sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 08/11/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities