

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>51N</u> R <u>36W</u>	<u>H11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 02/07/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H11) Quarter corner between Sections 27 and 34. 1848 - Established by S.W.Higgins, Deputy Surveyor. Set post midway and on the section line between Section corners 40.49 chains east and west. Birch 14 N20E 13 links, Sugar 10 S65E 16 links. ca. 1920's P.A.Larson sketch states " Set post from Root Sug S55E 10.6' down. Bir. 14" N20E 8.6'. In hole of old post". 1962 - Remonumented by Billy D. Buckler: "This corner replaced at old scribed wood post found by L.Stevens, District Forester in 1948. ... Believe this post is part of a survey made in the 1920's". Set 1" pipe with 4" aluminum cap. 12" Hard Maple S60E 26 links, 14" Y.Birch N28W 49 links, 15" Soft Maple S40W 48 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H11) Found the 1962 monument in good condition and at record bearing and distance from the 1962 witness Sugar SE (good condition with overgrown blazes) and Y.Birch NW (standing dead). The Maple SW was not apparent above the snow. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H11) Found 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 15" Sugar S51E 18.0' overgrown blazes 1962 NBT
 5" Y.Birch S28W 5.9' mrkd "1/4S NBT"
 6" Maple N60W 3.7' do
 10" Sugar N24E 25.5' do
 set sq'd cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 08/11/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities