

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 51N R 36W	H9
	T 51N R 36W	I10
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9								●					
10	30		29		28		27	●	26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on H9 05/20/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H9) Quarter corner common to Sections 22 and 27. 1848 - Established by S.W.Higgins, Deputy Surveyor, midway and on the true line between Section corners 40.48 chains east and west. Set post. Hemlock 8" N57W 16 links, Sugar 8" N86E 12 links.

(I10) Quarter corner common to Sections 26 and 27. 1848 - Established by S.W.Higgins, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains north and south. Set post. Balsam 10" N43E 13 links, Sugar 24' S20E 27 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H9) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2630.85' east and west, proportionate to the original record.

(I10) The original post and accessories were not recovered. Reestablished the corner midway and on the Section line between Section corners 2640.73' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H9) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Ash N09E 5.9' mrkd "1/4S NBT"
 6" Sugar S67E 26.7' do
 6" Sugar S19W 34.4' do
 15" Hemlock N64W 36.2' do
 Set sq'd cedar post adjacent. Bearings magnetic.

(I10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR cap in the side of:
 12" Sugar N03E 14.5' mrkd "1/4S NBT"
 5" Maple N84E 4.0' do
 11" Maple S06E 20.9' do
 5" Y.Birch S45W 16.4' do
 Set sq'd cedar post adjacent. Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 08/11/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities