

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Houghton</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 36W	111
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 34 T 51N R 36W	13
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11									●				
12		31		32		33		34		35		36	
13									●				

I, Stephan J. Szyszkoski, in a field survey on 13 06/10/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I11) Corner common to Sections 26-27-34-35. 1848 - Established by S.W.Higgins, Deputy Surveyor. Set post. Birch 30 S40W 6 links, Maple 24 N20W 32 links. 1962 - Remonumented by Billy D. Buckler RLS "from badly decayed birch stump which may have been original B.T. (30" Birch S40W, 06 links). Distances to corner N and S check good". Set 1" iron pipe with 4" brass cap. 5" H.Maple S82W 47 links, 5" S.Maple N63W 21 links, 7" Aspen S40E 05 links.

(13-Sec. 34) Southeast 1/16 corner, Section 34. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I11) Found the 1962 monument in good condition and at record bearing and distance from the 1962 NBT Maple NW, now 8" DBH, in good condition. The other two 1962 NBTs were not apparent above the snow. Accepted the monument as the best available evidence of the position of the original corner.

(13-Sec. 34) Established the corner at the intersection of 1/16th lines as described on a survey dated Aug. 6, 2008, Project Numbers 11-05-08 and 11-10-08, by the undersigned for the Michigan Dept. of Natural Resources.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I11) Found 1"ID iron pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 8" Maple N52W 14.0' overgrown blazes 1962 NBT
 6" Sugar N20E 32.1' mrkd "S26 NBT"
 8" Maple S48E 6.9' "S35 NBT"
 6" Maple S52W 12.9' "S34 NBT"
 Set sq'd cedar adjacent. Bearings are magnetic.

(13) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" twin Sugar N29W 26.35' mrkd "1/16S BT"
 9" Sugar N65E 17.95' do
 12" twin Sugar S04E 27.15' do
 7" Sugar S79W 16.2' do
 Set sq'd sugar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/11/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

