

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Houghton	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 51N R 36W	I13
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 27 T 51N R 36W	H10
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on I13 06/11/2008 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I13) Standard Section corner common to Sections 34 and 35 T51N-R36W, on the 5th Correction Line. 1845 - Established by Austin Burt, Deputy Surveyor. Set post. Sugar 14" N55E 22 links, Sugar 14 N03W 65 links. Ca. 1920's - P.A.Larson notes: Set cedar post. B.T. Sug N55E 14.3'. 1962 - Remonumented by Billy D. Buckler RLS at 1" iron pipe placed by Michigan State Highway Department. Set 1"ID I.pipe with 4" brass cap. 15" Hard Maple N02W 54 links, 7" Hard Maple East 48.5 links.

(H10) Center of Section 27. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I13) Found the 1962 monument in good condition and at substantial record bearing and distance from the 1962 witness trees, both in good condition with overgrown blazes. Accepted same as the best available evidence of the position of the original corner.

(H10) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I13) Found 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 17" Sugar N15E 36.2' old blazes. 1962 NBT
 10" Sugar S87E 32.0' do do
 9" Sugar S05W 22.9' mrkd "S6 NBT"
 8" Sugar N75W 29.1' "S34 NBT"
 Set sq'd cedar post adjacent. Bearings magnetic.

(H10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 16" Sugar N51E 7.35' mrkd "C1/4 BT"
 5" Y.Birch S15E 12.15' do
 11" Hemlock S45W 42.0' do
 6" Y.Birch N46W 13.1' do
 Set sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/11/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities