

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY


T 51N R 36W

DESCRIPTION OF CORNER Section Corner 2, 3, 10, and 11

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED October 20, 1970

WITNESSES TO CORNER..... Sugar Maple 12 S43°W (mag.) 40.3 ft. "S10, NBT"



Sugar Maple 8 N55°E (mag.) 30.1 ft. "S 2, NBT"

Sugar Maple 8 N29°W (mag.) 17.7 ft. "S 3, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner located from stumps of two probable original BT's. The only identifying marks on either is a possible scar overgrowth on the lower face of the NE BT, as both stumps are in poor condition. Both agree as to species, probably in relative size, and in bearing and distance with recorded originals. Position checks well with an original 1/4 corner 1/2 mile south, with lake margins to S and E, and with a stream crossing to N. Many old blazed trees in vicinity, with a 22" sugar maple with old blazes on 4 sides bearing S36°W 28½ lks. from corner. Old location tag on this tree, as well.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

March 21, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68