

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Houghton COUNTY
T 51N R 36W

DESCRIPTION OF CORNER 1/4 corner between Sections 1 and 2

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 13, 1970

WITNESSES TO CORNER..... Red Maple 6 S38°W (mag.) 5.0 ft. "1/4S, NBT"



Red Maple 4 N 2°W (mag.) 6.0 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner located from one original BT, a W. Pine 24 S87E 5, now a stump in good condition with scribe marks "1/4S" and "BT" visible on lower and upper blazes. An old blazed line goes N'ly from the pine stump.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE March 21, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68