


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD

Houghton COUNTY
T 51N R 36W

DESCRIPTION OF CORNER Section Corner 1, 2, 11, and 12
CORNER MONUMENT 1" I.D. x 36" Iron pipe with 4" aluminum cap. Corner pipe buried
1"-2" below ground level.
DATE MONUMENT PLACED AND WITNESSED October 20, 1970
WITNESSES TO CORNER..... Sugar Maple 16 N 8°E (mag.) 31.4 ft. "S 1, NBT"



Sugar Maple 7 S66½°E (mag.) 50.6 ft. "S12, NBT"
W. Spruce 4 N35°W (mag.) 25.1 ft. "S 2, NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by double proportionate measurement from corners 158.81 ch. S, 39.70 ch. N, 80.59 ch. E, and 80.19 ch. W. Found a 1" x 24" round iron pin lying in the road about 1 ch. SW'ly of corner, which may have once marked the corner, but impossible to tell where it came from. Corner lies just N'ly of N'ly track of woods road running SW and NE.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

March 21, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68