

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Houghton COUNTY
T 51N R 36W

DESCRIPTION OF CORNER South 1/16 corner between Sections 13 and 14

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED November 5, 1970

WITNESSES TO CORNER..... Sugar Maple 6 S32°W 15.1 ft. "1/16S, BT"



Red Maple 5 N55°W 16.2 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No evidence that the corner had been correctly established previously.

Corner established on line between section corner 19.854 ch. S and 1/4 cor. 19.854 ch. N. Found a 1" I.D. iron pipe possible intended to be this corner, but established N40 $\frac{1}{2}$ °W 1.37 from it, which was considered unacceptable. The corner position checks well with a stream crossing about 2 ch. S as mentioned in original field notes.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE March 24, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68