


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Houghton COUNTY  
T 51N R 36W

DESCRIPTION OF CORNER 1/4 corner between Sections 9 and 10  
CORNER MONUMENT Replaced the found pipe with a  
1" I.D. x 36" iron pipe with 4" aluminum cap  
DATE MONUMENT PLACED AND WITNESSED November 5, 1970

WITNESSES TO CORNER..... B. Spruce 6 S63°E (mag.) 12.1 ft. "1/4S, NBT"



Hemlock 12 N40°E (mag.) 42.5 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1/2" I.D. x 6" iron pipe in place as set by unknown surveyor and witnessed by B. D. Buckler, R. L. S. on 5/9/66.

Corner undoubtedly original. Rotted stump of spruce BT still present, with scrap of overgrowth and ingrown bark on a scribe mark remaining to identify it.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

Area Forester

District Surveyor

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE October 30, 1972