

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 51. NR. 36-37. W

Houghton COUNTY

DESCRIPTION OF CORNER Sec. corner for sections 18, 19, 13, 24

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 2-3-58

16" hard maple 41°, E 60 links. Marked "S18NBT"

14" hard maple N 27°, W 45 links. Marked "S13NBT"

11" hard maple, S 26°, W 60 links. Marked "S24NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR

RESTORED. Replaced from two probable B. T.'s. Maple stump bearing S 30°, W 21 links. Stump recently cut, bottom of scar visible in wood. Maple bearing S 35°, E 28 links. Tree green but rotted inside; has been chopped out many years ago. Numerous blazes in vicinity. Position checks with streams to north.

SURVEYORS SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler
REGISTERED LAND SURVEYOR
DATE 5-1-59