

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 51. NR. 26. W

Houghton COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 17, 18, 19, and 20

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 6" Black Spruce (S 18 NBT) N 12° W 36 Links

7" Black Spruce (S 17 NBT) N 56° E 32 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED. This corner was re-established using Section corners 1 mile east;
1 mile west, and swamp edge 2.00 chains north. No evidence of original corner.
Corner lies in north edge of spruce swamp.

Corner was placed and witnessed October 12, 1959 with Frank J, Bray.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 2/26/60

Billy D. Buckler