

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 51. NR. 26. W

H o u g h t o n COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 16, 17, 20 and 21

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 6" Sugar Maple (S 17 NBT) N 25° W 43 1/2 Links

8" Sugar Maple (S 21 NBT) S 32° E 34 1/2 Links

12" Sugar Maple (S 16 NBT) N 45° E 50 Links

12" Blackcherry (S 20 NBT) S 44° W 22 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED. This corner was replaced at old corner which was used for some time.
Yellow Birch Stump found with notch also piece butted had old blazes. Corner
seems to fit with original B. T. 1/4 corner to north and stream to east. Found
Keweenaw Land Association tag at corner.

Corner was placed and witnessed October 8, 1959 with F. Bray, Engr. Aide I.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2/29/60
REGISTERED LAND SURVEYOR
Billy D. Buckler