

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 51. NR. 36. W.

H o u g h t o n COUNTY

DESCRIPTION OF CORNER 1/4 corner between Section 6 and 7

DESCRIPTION OF CORNER MONUMENT 1" Iron Pipe with 4" Brass Cap

WITNESSES TO CORNER 8" White Pine (1/4s NBT) S 88° E 49 Links

9" White Pine (1/4s NBT) S 73° E 1.12 chains

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED. This corner was replaced from one Tamarack B. T. bearing N 60° W
18 Links. Stump in good condition. Corner lies in swamp.

Corner was placed and witnessed October 7, 1959 with Frank Bray, Engineering Aide I.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 2/29/60
REGISTERED LAND SURVEYOR
Billy D. Buckler