

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 51N N.R. 36W


Houghton COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 27-34

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 10-2-62

WITNESSES TO CORNER..... 12" Hard Maple (1/2 S NBT) S60°E 26 links



14" Y. Birch (1/2 S NBT) N28°W, 49 links

15" Soft Maple (1/2 S NBT) S40°W, 48 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at old scribed wood post found by L. Stevens, D. F. in 1948. Distance east to section corner is good. Distance west to stream is slightly longer than record. Believe this post is part of a survey made in the 1920's.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 26, 1963  
REGISTERED LAND SURVEYOR

Billy D. Buckler