

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 51N N.R. 36W


Houghton COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 28-33

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 10-8-62

WITNESSES TO CORNER..... 13" aspen (1/2 S NBT) N85°E, 42 links



50" W. Pine Stp. (NBT) N48°E, 60 1/2 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established on line and record distance from a section corner 1/2 mile to west. This position agrees with testimony of James O'Mara, Nisula, a former owner of adjacent land. Mr. O'Mara visited this site with me on this date. Found several blazes east and west of corner. The 1/2 mile to east is short (6.72 chains) due to an error in the original survey.

SURVEYOR'S SEAL

SIGNED Billy D. Backler DATE April 26, 1963
REGISTERED LAND SURVEYOR
Billy D. Backler