

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 51N N.R. 36W


Houghton COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 28-29

CORNER MONUMENT 1" pipe with 4" brass cap,

DATE MONUMENT PLACED AND WITNESSED 9-6-62

WITNESSES TO CORNER..... 12" Y. Birch (1/2 S NBT) S25°E, 32 links



11" Cedar (1/2 S NBT) N60°W, 81 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner placed at 2 old wood posts with a cedar stump bearing S30°E, 25 links. Stump in poor condition. Found an old turnout in proper position for hemlock B.T. Found Cedar line tree 1.48 chs North of corner to correspond with record field notes.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 24, 1963
REGISTERED LAND SURVEYOR
Billy D. Buckler