

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

HOUGHTON COUNTY				CORNER CODE NUMBER
FOR CORNERS OF --:	LOCATED IN --:			
1. PUBLIC LAND SURVEY _____	T. 51	N. 36	W. 36	I12, J12
2. PROPERTY CONTROLLING IN SECTION _____	T. 51	N. 36	W. 36	10
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____	N. _____	W. _____	
4. LOT NO. _____, RECORDED PLAT _____				
5. PRIVATE CLAIMS _____				

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 10, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner I12: Original monument and accessories not found.
 - Corner 10: Not set on original survey. Found old iron pipe S88-28-37W 27.09 ft. set by unknown person.
 - Corner J12: Not set on original survey. Found iron pipe S52-40-34W 130.28 ft.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner I12: Restored on line midway between corners north and south.
 - Corner 10: Established midway and on line between corners north and south.
 - Corner J12: Established during section subdivision.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | |
|--|--|
| Corner I12: Set 1" I.D.x32" iron pipe with 4" alum. cap.
4" Sugar N51E 8.5 ft. 1/8S,NBT
6" Sugar N51N 5.8 ft. 1/8S,NBT
7" Sugar S01W 15.7 ft. 1/8S,NBT | Corner J12: Set 1" I.D.x32" iron pipe with 4" alum. cap.
7" Sugar N23W 8.2 ft. 1/8S,BT
14" Sugar S38E 14.2 ft. 1/8S,BT
9" Sugar N88W 29.1 ft. 1/8S,BT |
| Corner 10: Set 1" I.D.x32" iron pipe with 4" alum. cap.
5" Sugar S40E 23.3 ft. 1/16S,BT
7" Sugar S32W 18.0 ft. 1/16S,BT
5" Maple N50W 10.3 ft. 1/16S,BT | |

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)
 FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-26-82
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

