

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

HOUGHTON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> <sup>N.</sup> / <sub><del>N.</del></sub> , R. <u>36</u> <sup>E.</sup> / <sub>W.</sub>	G12
2. PROPERTY CONTROLLING IN SECTION <u>35</u>	, T. <u>51</u> <sup>N.</sup> / <sub><del>N.</del></sub> , R. <u>36</u> <sup>E.</sup> / <sub>W.</sub>	5, 3
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> / <sub>S.</sub> , R. _____ <sup>E.</sup> / <sub>W.</sub>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 11, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner G12: **Original monument and accessories not found.**
  - Corner 5: **Not set on original survey nor subsequently apparently.**
  - Corner 3: **Not set on original survey nor subsequently apparently.**
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner G12: **Restored midway and on line between corners north and south.**
  - Corner 5: **Established during section subdivision.**
  - Corner 3: **Established during section subdivision.**
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner G12:  $\frac{1}{4}$  Corner is a 24" Sugar
    - 6" Sugar N71E 23.5 ft.  $\frac{1}{8}$ S,NBT
    - 3" Sugar N36W 18.5 ft.  $\frac{1}{8}$ S,NBT
    - 7" Sugar S23W 20.5 ft.  $\frac{1}{8}$ S,NBT
  - Corner 3: **Set 1" I.D. by 32" iron pipe with 4" alum. cap.**
    - 7" Sugar N16W 12.9 ft. 1/16S,BT
    - 7" Sugar S24W 15.6 ft. 1/16S,BT
    - 6" Sugar S23E 20.9 ft. 1/16S,BT
  - Corner 5: **Set 1" I.D. by 32" iron pipe with 4" alum. cap.**
    - 3" Sugar N11E 8.5 ft. 1/16S,BT
    - 5" Sugar S74E 15.2 ft. 1/16S,BT
    - 5" Sugar S20W 19.1 ft. 1/16S,BT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-26-82  
CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett  
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

