

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

HOUGHTON COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER	
1. PUBLIC LAND SURVEY	T. 51 N. R. 36 W.	M-2	M-1
2. PROPERTY CONTROLLING IN SECTION 1	T. 51 N. R. 36 W.	7	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.		
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-12- 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner M-2: Original monument and accessories not found. Found Keweenaw Land location poster north 33 ft.
 - Corner M-1: Original monument and accessories not found. Found probable line tree 20 chains north.
 - Corner 7: Not set on original survey nor subsequently apparently.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner M-2: Restored on line by proportion between section corners north and south.
 - Corner M-1: Restored by double proportion between corners and land calls. Location fits good with land calls and other corners in area.
 - Corner 7: Established on line by proportion between section corner north and 1/4 corner south.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | |
|--|---|
| Corner M-2: Set 1" I.D. by 32" Iron Pipe w/ 4" alum. cap.
3" Sugar S12W 36.8 ft, 1/4S NBT
1" Y. birch N39E 21.0ft 1/4S, NBT
1" Sugar N29W 17.0 ft 1/4S, NBT | Corner M-1: Set 1" I.D. by 32" Iron Pipe w/4" alum. cap.
9" hemlock S58E 19.3 ft S6, NBT
10" w.pine N70W 2.6 ft S36, NBT
4" Maple S04W 15.2 ft S1, NBT |
| Corner 7: Set 1" I.D. by 32" Iron pipe w/4" alum. cap.
1" Y. birch N18E 5.6 ft 1/16S, BT
1" Sugar S88W 16.5 ft 1/16S, BT
3" Hemlock S42E 13.1 ft. 1/16S, BT | |

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 2-16-83

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

