

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

HOUGHTON COUNTY

| FOR CORNERS OF--                      | LOCATED IN--      | CORNER CODE NUMBER |
|---------------------------------------|-------------------|--------------------|
| 1. PUBLIC LAND SURVEY                 | T. 51 N. R. 36 W. | G4, G5, H5, G6     |
| 2. PROPERTY CONTROLLING IN SECTION    | T. S. R. E. W.    |                    |
| 3. MISCELLANEOUS PROPERTY IN SECTION  | T. S. R. E. W.    |                    |
| 4. LOT NO. _____, RECORDED PLAT _____ |                   |                    |
| 5. PRIVATE CLAIMS _____               |                   |                    |

Houghton Co

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3-22-83, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- Corner G4: Found DNR monument set from original bearing tree; spruce 14" N30W .17 CH; by Billy D. Buckler 5-9-66.
- Corner G5: Original monument and accessories not found.
- Corner H5: Original monument and accessories not found.
- Corner G6: Original monument and accessories not found.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- Corner G4: Restored from original B.T.
- Corner G5: Restored by double proportion distance.
- Corner H5: Restored on line midway between corners east and west.
- Corner G6: Restored on line midway between corners north and south.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |   |   |
|---|---|
| <p><b>Corner G4:</b> 1" ID by 36" iron pipe w/4" alum. cap.<br/>6" Spruce S56E 11.9 ft. 1/4S NBT<br/>5" Cedar N22E 29.5 ft. 1/4S, NBT<br/>8" Hemlock N89W 15.1 ft. 1/4S, NBT</p> <p><b>Corner G5:</b> Set 1" I.D. by 32" iron pipe w/4" alum. cap.<br/>14" Cedar N15W 8.4 ft. S9, NBT<br/>7" Cedar N52E 5.8 ft. S10, NBT<br/>7" Balsam S38W 17.6 ft. S16, NBT</p> | <p><b>Corner H5:</b> Set 1" I.D. by 32" iron pipe w/4" alum. cap.<br/>16" Cedar S57E 47.1 ft. 1/4S, NBT<br/>5" Sugar S15W 24.1 ft. 1/4S, NBT<br/>5" Y. Birch N15W 3.6 ft. 1/4S, NBT</p> <p><b>Corner G6:</b> Set 1" I.D. by 32" iron pipe w/4" alum. cap.<br/>5" Spruce N69W 14.2 ft. 1/4S, NBT<br/>7" Balsam N89E 3.0 ft. 1/4S, NBT<br/>5" Balsam S30E 3.9 ft. 1/4S, NBT</p> |
|---|---|

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006