

**LAND CORNER RECORDATION CERTIFICATE**  
**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

Heughton County FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. <u>51</u> N. E. R. <u>36</u> W.	<u>E2</u>
2. PROPERTY CONTROLLING IN SECTION <u>5</u>	T. <u>51</u> N. E. R. <u>36</u> W.	<u>7</u>
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 30, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E2: Original monument and accessories not found.

Corner 7: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E2: Restored by proportion on line between corners north and south.

Corner 7: Established by proportion on line between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E2: Set 1" I.D. by 32" I.P. with 4" aluminum cap.

5" sugar S07E 5.0' 1/8, MBT  
 4" sugar N26E 10.2' 1/8, MBT  
 18" spruce S80W 19.6' 1/8, MBT

Corner 7: Set 1" I.D. by 32" I.P. with 4" aluminum cap.

4" sugar N27E 18.0' 1/16 S, BT  
 9" sugar S46W 19.9' 1/16 S, BT  
 5" sugar S40E 37.8' 1/16 S, BT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 2-4-85

CHIEF OF SURVEY PARTY  
 Keith L. Sackett  
 Michigan Registered Land Surveyor  
 Department of Natural Resources

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006