

**LAND CORNER RECORDATION CERTIFICATE**  
**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

Houghton County

FOR CORNERS OF --:

LOCATED IN --:

CORNER CODE NUMBER

1. PUBLIC LAND SURVEY \_\_\_\_\_ T. 51 N. 36 E. R. 36 W. C1, C2

2. PROPERTY CONTROLLING IN SECTION 5 T. 51 N. 36 E. R. 36 W. 3

3. MISCELLANEOUS PROPERTY IN SECTION \_\_\_\_\_ T. \_\_\_\_\_ N. \_\_\_\_\_ E. S. R. \_\_\_\_\_ W.

4. LOT NO. \_\_\_\_\_, RECORDED PLAT \_\_\_\_\_

5. PRIVATE CLAIMS \_\_\_\_\_

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C3: Found monument set by Billy D. Buckler in 1960.

Corner C2: Original monument and accessories not found.

Corner 3: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C3: Restored 1-10-85 at monument. Corner falls near center of transmission clearing.

Corner C2: Restored 1-30-85 by proportion on line between corners north and south.

Corner 3: Established 1-30-85 by proportion on line between corners north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C3: 1" pipe with 4" brass cap. 12" sugar N56E 71.9' S5, MBT  
 14" sugar S82E 77.5' S8, MBT  
 Center power pole N11W 6.6'

Corner C2: Set 1" I.D. by 32" I.P. with 4" aluminum cap. 7" sugar S52E 23.4' S, MBT  
 8" sugar N34E 28.4' S, MBT  
 7" sugar S09E 41.2' S, MBT

Corner 3: Set 1" I.D. by 28" I.P. with 4" aluminum cap. 5" maple S28W 10.0' 1/16S, BT  
 7" maple N70E 4.2' 1/16S, BT  
 4" maple S11E 24.3' 1/16S, BT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 2-4-85

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett  
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 10006