

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Naughton

(County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>S1N</u> R <u>36M</u>	<u>F1, F2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>4</u> T _____ R _____	<u>14, 13</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Keith L. Backett, in a field survey on December 20, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

F1	F2	14	13
Original monument and accessories not found.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.	Not set on original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F1	F2	14	13
Restored on line by proportion between section corner west and west 1/16 between 34/3.	Established during section subdivision.	Established on line between section corner east and 1/4 corner west at record distance from lake shore which doesn't appear to have moved.	Established during section subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F1	F2	14	13
Set 1" I.B. by 36" I.P. w/4" aluminum cap.	Set 1" I.B. by 32" I.P. w/4" aluminum cap.	Set 1" I.B. by 36" I.P. w/4" aluminum cap.	Set 1" I.B. by 32" I.P. w/4" aluminum cap.
12" sugar N89W 27.2ft. 1/48, NBT	7" maple N330 2.0ft. 1/48, BT	3" sugar S26E 3.9 ft. 1/168, BT	6" sugar N79W 2.2ft. 1/168, BT
6" sugar S13E 26.2ft. 1/48, NBT	4" sugar S72E 5.3ft. 1/48, BT	6" sugar N01E 5.0ft. 1/168, BT	4" sugar S05E 8.9ft. 1/168, BT
7" maple N30E 14.0ft. 1/48, NBT	5" maple N54W 7.4ft. 1/48, BT	5" sugar N54W 11.0ft. 1/168, BT	12" N. Pine N75E 10.2ft. 1/168, BT

Signed by Keith L. Backett Date _____

Surveyor's Michigan License No. 19006

