

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
1 Houghton
 (County)
 Located In: _____ Corner Code ## _____

1	Public Land Survey	T 51N	R 36W	<u>K5</u>
		T _____	R _____	_____
		T _____	R _____	_____
		T _____	R _____	_____
2	Property Controlling in Section	S _____	T _____	R _____
		S _____	T _____	R _____
3	Miscellaneous Property in Sec.	S _____	T _____	R _____
		S _____	T _____	R _____

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

I, Keith Sackett, in a field survey on April 25, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K5
 Found old monument, bent pipe and broken cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K5
 Restored from the two yellow birch stumps and pushed over ironwood stump.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K5
 Set 1" ID x 32" iron pipe w/4" aluminum cap. Measurement good from S-W random line 94.38'
 5" yellow birch S07W 16.6' s14, NBT
 6" maple S61W 31.6' s14, NBT
 5" maple S55E 36.1' s13, NBT

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Keith Sackett

Date

August 27, 1990

Surveyor's Michigan License No. _____

19006