

91

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Noughton

Located in:

Corner Code #

(County)

1. Public Land Survey

T 51N R 36W E4

T R

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

May 10 1995

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5		4		3		2		1			
3													
4	7	8		9		10		11		12			
5													
6	16	17		16		15		14		13			
7													
8	19	20		21		22		23		24			
9													
10	30	29		28		27		26		25			
11													
12	31	32		33		34		35		36			
13													

A. Description of original monument and accessories and/or subsequent restoration:  
Quarter corner common to Sections 8-9. Corner reestablished in 1959 by Billy D. Buckler as follows: "This corner was re-established midway and on line between two Section corners. No evidence of original corner. Found old blazes north and south of corner. Corner was placed and witnessed September 1, 1959" Buckler placed a 1" pipe with 4" brass Michigan Dept. of Conservation tablet and the following bearing trees: 12" Hard Maple (1/4S NBT) S02E 42 links, 12" Hard Maple (1/4S NBT) N76W 42 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Buckler's monument was not recovered. Remonumented the corner from the 1959 NBTs, recovered as follows: 16" Sugar N75W (mag.) (rec. as N76W), 42 links, found in good condition with blazes completely overgrown. Chopped out blaze to observe scribing "1/4S" in BH blaze. Overgrowth is about 7" thick. Found stump remains of 12" Sugar due south (mag.) (rec. as S02E) 42 links. This tree was cut long ago. Although no markings were found on the stump, I presume it to be the 1959 NBT. At the position for the corner, I placed a 1" I.D.x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1" pipe with 4" MDNR cap. Blazed

and scribed the following:

16" Sugar N75W 27.1' "1/4S NBT" below  
the chopped out 1959 blaze.

8" Sugar N11E 30.4' "1/4S NBT"

8" Sugar N75E 9.1' "1/4S NBT"

7" Sugar S27E 22.2' "1/4S NBT"

Set a location poster on a 9" sugar with  
old blazes S73E 14'. Placed a 6" cedar  
post adjacent. Bearings are magnetic.



Signed by

*Stephan J. Szyszkoski*

Date

5-10-95

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division